

ADDENDUM NUMBER 1

<u>PROJECT</u>	<u>BIDS DUE</u>
Zwischendorf Trail Water Main Extension Mancelona Area Water & Sewer Authority	Date: August 15, 2013 Time: 1:00 PM Location: MAWSA Office 9610 S. M-88 Hwy., Mancelona, MI 49659
GFA Project No: 12436	

The Addendum is issued prior to the Receipt of bid proposals to amend the Contract Documents as follows. Bidders shall acknowledge receipt of this addendum by means of a hand written note on the Bid Schedule.

1. Section 02510 Clarification:
 - Diagram "A" attached to this addendum, shall be incorporated into Section 2510 and included with the bid documents.
 - Service Lead Clarification: 1" HDPE DR 9 water service leads to be installed, in addition to the Type K copper. The piping shall be NSF compliant and have a minimum operating pressure of 200 psi. In addition, a continuous, insulated 10-gauge wire shall be laid in the trench along with the plastic pipe, with both ends exposed at the termination points of plastic pipe.
 - Meter Installation Clarification: It is preferred meters to be installed in homes, however Contractor is responsible for coordination and communication with property owner to allow. In event that meters cannot be installed in homes, meter pits are to be utilized with locations to be field determined. Contract shall be adjusted via Change Order to accommodate actual quantities of meter pits that need to be installed.
2. Terms of Payment: This project is funded utilizing money from the Michigan Department of Environmental Quality. The contractor shall anticipate receipt of payment based upon MDEQ processing time of pay applications, which can take up to 90 days.

This Addendum No. 1 becomes part of the Contract Documents as of this date and supersedes the information in the originally issued Contract Documents, where applicable. The Contractor shall acknowledge receipt of the Addendum on the Bid form (Section 00400) included with his/her bid.

DIAGRAM "A"

