

**ADDENDUM NUMBER 1**

<u>PROJECT</u>	<u>BIDS DUE</u>
GFA Project No: 22070 River East Recreation Area Improvements – Phase II RFP	Date: August 16, 2022 Time: 10:00 AM Location: Charter Township of Garfield 3848 Veterans Drive, Traverse City, MI 49684

The Addendum is issued prior to the receipt of bid proposals to amend the Contract Documents as follows. Bidders shall acknowledge receipt of this addendum by means of a handwritten note on the Bid Schedule.

[www.gfa.tc](http://www.gfa.tc)

[www.garfield-twp.org](http://www.garfield-twp.org)

REQUEST FOR PROPOSAL

CLARIFICATIONS:

Contractor shall provide all equipment and materials as necessary to complete the work outlined in the proposal. The following clarification is noted below.

Schedule

- Township would prefer project completion this year 2022 but would allow for completion in 2023 by June 1<sup>st</sup> depending on material and labor availability. Contractor shall stipulate schedule on their bid form

Fence:

- Fence installation to include 1 ft over excavation and placement of fencing below grade, with 5 ft tall fence above grade. Overall Height of 6' to apply to both fence and gates. Refer to the specifications and details on Sheet 4.1.
- Fence Fabric to be provided with vinyl coating, color black

SPECIFICATIONS

Specification 02821, Section 2.1. A: The following section shall be removed and replaced with the following:

- A. General: 6 feet (5' Exposed and 1' Buried). Provide fabric in one-piece heights measured between top and bottom of outer edge of selvage knuckle or twist. Comply with ASTM A 392, CLFMI CLF 2445, and requirements indicated below:
  1. Steel Wire Fabric: Vinyl-coated wire with a diameter of 0.120 inches. Color: Black
    - a. Mesh Size: 2 inches.
    - b. Coating: ASTM A 392, coating applied after weaving.

Specification 02821, Section 2.2. B: The following section shall be removed and replaced with the following:

- A. Frames and Bracing: Fabricate members from round, galvanized steel tubing with outside dimension and weight according to ASTM F 1184 and the following:
  1. Gate Fabric Height: 6 feet. (5' Exposed and 1' Buried)  
Gate Opening Width: 4 feet and 8 feet as denoted on the plans
  2. Frame Members:
    - a. Tubular Steel: Size as required.
  3. Bracing Members:
    - a. Tubular Steel: Size as required.

This Addendum No. 1 becomes part of the Contract Documents as of this date and supersedes the information in the originally issued Contract Documents where applicable. The Contractor shall acknowledge receipt of the Addendum in the Bid Schedule included with his/her bid.